



Corporate Hazard Identification & Risk Control

HIRA #
15.49

Mount or Dismount of Construction Equipment

Applicable Zones:	Project	X	Yard		Office		Asphalt Plant	
--------------------------	---------	--------------	------	--	--------	--	---------------	--

HAZARD(S)

- Slip, Trip or Fall (P)
- Musculoskeletal Disorders (P)

PRE-CONTROL RISK

Likelihood 3	Consequence 4	Pre-Control Risk 12
-----------------	------------------	--------------------------------

CONTROLS

Elimination

Substitution

Engineering

Always mount and dismount facing the cab (unless in an emergency situation)
Keep three points of contact while mounting and dismounting.

Administrative

PPE

High Visibility Clothing, Hard Hat & Safety Boots at a minimum must be worn at all times.
Ensure footwear is in good condition.

POST CONTROL RISK

Likelihood 1	Consequence 4	Post-Control Risk 4	Risk Reduction 8	Critical or Not Critical No
-----------------	------------------	--------------------------------	---------------------	--------------------------------

LEGISLATIVE REFERENCES

O.Reg. 213/91: S. 72
O.Reg. 213/91: S. 93
O.Reg. 213/91: S. 94(2)
O.Reg. 213/91: S. 95(1,2)
O.Reg. 213/91: S. 97
O.Reg. 213/91: S. 101

OTHER STANDARDS & REFERENCES

J-AAR Manual
P1.4.18 P1.5.4.18
P2.11.8 P2.12.11.8
P2.11.9 P2.12.11.9