



# Corporate Hazard Identification & Risk Control

HIRA #  
15.55

## Objects Stored Improperly

<b>Applicable Zones:</b>	Project	<del>Yard</del>	<del>Office</del>	Asphalt Plant
--------------------------	---------	-----------------	-------------------	---------------

### HAZARD(S)

- Falling Equipment (P)
- Struck By (P)
- Terrain Instability (P)

### PRE-CONTROL RISK

Likelihood 3	Consequence 5	<b>Pre-Control Risk 15</b>
-----------------	------------------	--------------------------------

### CONTROLS

<b>Elimination</b>	Ensure tools and equipment are stored and put away properly and securely.
<b>Substitution</b>	
<b>Engineering</b>	
<b>Administrative</b>	A level area extending at least 1m from the top of the excavation shall be kept clear of equipment and material.
<b>PPE</b>	High Visibility Clothing, Hard Hat & Safety Boots at a minimum must be worn at all times.

### POST CONTROL RISK

Likelihood 1	Consequence 5	<b>Post-Control Risk 5</b>	Risk Reduction 10	Critical or Not Critical No
-----------------	------------------	--------------------------------	----------------------	-----------------------------------

### LEGISLATIVE REFERENCES

Mines and Mining Plants  
O.Reg 854  
Construction Regulations  
O.Reg 213/91  
Confined Spaces  
O.Reg 632/05

### OTHER STANDARDS & REFERENCES

J-AAR Manual: P1.4.10