



Corporate Hazard Identification & Risk Control

HIRA #
15.57

Poor Site Planning

Applicable Zones:	Project	X	Yard		Office		Asphalt Plant	
--------------------------	---------	--------------	------	--	--------	--	---------------	--

HAZARD(S)	
<ul style="list-style-type: none"> • Struck By (P) • Collision (P) 	

PRE-CONTROL RISK		
Likelihood 2	Consequence 4	Pre-Control Risk 8

CONTROLS	
<p>Elimination Site plan must be developed prior to starting the work.</p> <p>Substitution</p> <p>Engineering A signal person shall be designated whenever backing up is required.</p> <p>Administrative Every project shall be planned and organized so that vehicles, machines and equipment are not to be operated in reverse or operated in reverse as little as possible.</p> <p>PPE High Visibility Clothing, Hard Hat & Safety Boots at a minimum must be worn at all times.</p>	

POST CONTROL RISK				
Likelihood 1	Consequence 4	Post-Control Risk 4	Risk Reduction 4	Critical or Not Critical No

LEGISLATIVE REFERENCES	OTHER STANDARDS & REFERENCES
<p>O.Reg. 851: S. 11-20</p> <p>O.Reg. 854: S. 251-293</p>	<p>J-AAR Manual: P2.11.8</p> <p>J-AAR Manual: P2.11.9</p> <p>J-AAR Manual: P2.12.11.8</p> <p>J-AAR Manual: P2.12.11.9</p>